

Plumbing Pipe Takeoff

CSI Division 22 — Sample Quantity Takeoff

Item Description	Unit	Quantity	Notes
Copper Pipe, Type L	LF	1,860	Domestic water supply
PVC Pipe, DWV	LF	2,240	Sanitary waste + vent
Plumbing Fixtures	EA	64	WC, lav, sink, floor drain
Water Heaters	EA	3	Commercial, 100 gal
Pipe Insulation	LF	1,400	Hot water lines

This is a representative sample for portfolio purposes. The Best Estimator LLC.